

**Schedule of Quantity.**

Name of work:- Providing LIS to Bhat gran ,Tuni Seri, Bashona and Bagicha in GP Bashona in Tehsil and Distt. Kullu (H.P.) (SH:- Site development, beautification and land scaping around Pump house and desilting tank)

Etimated Cost 841620/-  
Earnest Money 16832/-  
Time 3 Months

Sr no.	Description of items	Quantity	Rate	Unit	Amount
1	Excavation in foundation trenches etc. in all kinds of soil such as pick work ,jumper work , soft/ hard blasting , chiselling wedging out of rock where blasting is prohibited & stacking the excavated soil clear from the edge of excavation & then returning the stackerd soil in 15 cm layers when required in to sides of foundation and plinth & consolidation of each deposited layers by ramming and watering and then disposing of all surplus excavated earth with in all leads of and lifts and to the entire satisfaction of Engineer in charge. (Pick jumper work 50% each)	89.72		cum	
2	P/L cement concrete 1:4:8( 1 cement 4 sand 8 graded stone aggregate 40 mm nominal size) and curing complete excluding the cost of form work in foundation and plinths	26.56		Cum	
3	Random rubbe masonry polygonal rubble masonry (uncomsed/ brought to covered ) with hand stone of approved quality foundation and plinth including levelling up with cement concrete 1:6:12 (1cement:6sand:12 graded stone aggregate 20mm nominal size) 1 cement mtrs 1:6(1cement, 6 sand) breast wall retaining walls.	147.54		cum	
4	Supply and stacking good earth at site including royalty and carriage upto 100 mtr on head load and 1 km by mechanically transport (earth work stock will be reduced 20% for payment)	503.11		cum	
5	Supply and stacking at site including royalty and carriage upto 100 mtrs on head load and 1 Km by mechanically transpost (sludge measured in stacks will be reduced by 8% for payment)	120.10		cum	
6	Suppling and stacking at site dump manure from approved sources (duly screened through specified sieve) including carriage upto 100 metres on head load and 1 km. By mechanical transport (manure measured in stacks will be reduced by 8% for payment)	120.10		cum	
7	Providing and laying cement concrete 1:11/2 :3 ( 1cement: 1 1/2 sand: 3graded stone aggregate 20 mm nominal size )and curing complete excluding the cost of form work and reinforcement in:-				
	l) Foundation and plinth.	5.10		Cum	
8	Providing tor steel reinforcement for RCC work including bending, binding and placing in position complete up to floor two level.	179		Kg	
9	Providing Stone pitching in horizontal portion and slopes of guid banks and protection works with in all leads and lifts to the entire satisfaction of Engineer in charge.	68.85		Cum	
10	Spreadubg sludge dump manure or /and good earth in required thickness (cost of sludge, dump manure or /and good earth to be paid seperately)	967.31		cum	
11	Grassing with 'Doob' grass including watering and maintenace of the Lawn for 30 days of more till the grass from a thick lawn free from weeds and fit for moving including supplying good earth if needed (the cost for Doob grass shall be paid seperately) In rows 7.5cm Apart in either direction. 15 cm	2307.50		Sqm	

**TERMS AND CONDITIONS.**

- 1 The work should be carried out as per PWD specification.
- 2 Nothing will be paid for rejected work / material.
- 3 10% security, 2% l/tax,& 2% s/tax & 1% cess will be deducted from the contractor payment.
- 4 Cement will be issued to the contractor @ 225/- per bag at IPH store Shamshi
- 5 GI pipes and fittings will be issued to the conotractor free of cost at IPH store, Shamshi
- 6 Steel will be issued to the contractor @ 4600/- per qtl. at IPH store, Shamshi

Executive Engineer  
IPH Division No.II  
Kullu at Bhunter