

SOQ Job-14

**SCHEDULE OF QTY.**

Name of Work:-R/M of various T/wells under Takka Section in IPH Sub Division No.I Una in Distt. Una H.P  
(Sub head:- Repair, Maintenance with operation of Pumping machinery with allied accessories for One Year. )

Estimated Cost Rs. 405000 only  
Earnest money Rs. 8100 only.  
Time One year

S.No.	Description.	Qty.	Rate	Unit	Amount.
1	Repair and maintenance of Centrifugal/ Submersible Pumping sets as per detail given below including rewinding of motor and replacement of any part related with pumping machinery, Panel board accessories such as panel Board, device,wire cable, all valves, Ampere Meter, Voltmeter, Pressure gauge, ICTP switches, Circuit breaker, Power Factor Capacitor, starter, Hour meter and any other gadgets fixed in the pump house to be kept operative without any leakage/fault in respect of the following schemes	150.00		HP	Per HP

	Name of scheme	Pumping machinery detail	No. of set.	B.H.P.	Total BHP
1	Tube well No.20 Takka	Submersible	1	15	15
2	Tube well at Bhalola	Submersible	1	35	35
3	Tube well No.26 Batuhi	Submersible	1	35	35
4	Tube well at Upper Basal Nr.S/Station	Submersible	1	17.5	17.5
5	Tube well at Takka	Submersible	1	30	30
6	Tube well at Upper Basal	Submersible	1	17.5	17.5

**Total 150.00**

**For operation**

Operation with watch & ward for 24 hours

LS

	Name of scheme	Operation of following P/Mach.
1	Tube well No.20 Takka	Submersible
2	Tube well at Bhalola	Submersible
3	Tube well No.26 Batuhi	Submersible
4	Tube well at Upper Basal Nr.S/Station	Submersible
5	Tube well at Takka	Submersible
6	Tube well at Upper Basal	Submersible

**TERMS & Conditions ( Att.)**

Note:- The rates should not be exhibited to contractors/ firms while issuing the SOQ.

Executive Engineer  
IPH Div. No.1 Una.