

Name of Work:- Providing LWSS Kehanwal. Kathlag, Chambi Jola tehsil Sadar Distt Mandi HP. (SH:-Providing and laying MSERW/GI pipe for Rising main for Booster stage, 1sr and 2nd stage.)

Terms and Conditions:-

1. Conditional and telegraphic tender are liable to be rejected.
2. All pages of tender form must be signed before submitting the tender failing which the tender is liable to be treated as invalid.
3. The work will be executed as per HPPWD/HPIPH specification, relevant IS codes and CPHEEO manual to the satisfaction of the Engineer-in-Charge.
4. The security, income tax sale tax and surcharge if any will be deducted from each Running bill of the contractor/firm.
5. All necessary documents such as income tax clearance certificate, renewal of registration CST/GST number will have to be produced by the contractor/firm before purchase of tender documents.
6. The rate of all the items should be inclusive of all taxes, duties, levies carriage of material within all leads and lifts etc to site of work.
7. When the pipe is supplied within the tolerance permitted by IS codes, the payment for negative side will be made on pro-rata different of weight derived on through rate but nothing extra will be paid for positive side.
8. The bends of required degree shall be provided by the contractor/firm whenever required as per direction of Engineer-in-Charge. The bends manufactured from parent taking care that nominal bore is not reduced or it will be rejected and shall be 100% test checked by Executive Engineer before burring.
9. The tenderer should ascertain the availability of MSERW/SAW pipes as per schedule of quantity before quoting their rates.
10. Test certificate, inspection and specification.
 - (a). The tenderer will have to produce manufacturer's test certificate for all apperteneousess.
 - (b). 3rd party inspection will be got done from one of the following:-
 1. Rates, 2. Dentnorsake Varitas. 3 Bureau Variats, 4 SGS, 5 M/S Quality Service and Solution new Delhi.
 - (c). Payment only for the accepted and fully tested work will be released.
 - (d). The pipes will be measured and weighted in the presence of authorized representative of the department at site//weigh Bridge. The documents showing then laden and un-laden weights and lengths will be submitted to Engineer-in-Charge alongwith post delivery bill.
11. Any damage caused to any public/private property during the course of execution of work shall be Restored by the contractor and if not done within a reasonable time then the same will be restored by the department at contractors cost.
12. L-section and plan of pipe line can be seen in the Divisional office on any working day. Whoever contractor shall visit the site and work out filled detail for laying of pipe lines as per site conditions and should quote is rates according.
13. Contractor will arrange his own power connecting whenever required.

Executive Engineer,
IPH Division Mandi.